



North

KEY TO SURVEY CODES			
Condition	Symbol	Fault Type	Severity
Coating	CT	Coating	Not applicable
	CTF	Coating Failed	Area in sq. ft.
Cracks	C	Crack	Width in 1/16" increments
	CJ	Crack system: Joints	0 Hairline
	CU	Crack system: Units	.5 Hairline to 1/32 inch
	CUJ	Crack sys.: Units & Joints	1 1/32 to 1/16 inch
	CRPr	Crack Repair	2 1/16 to 1/8 inch
	CRPrF	Crack Repair Failed	Sev Severs
Displacement	Hor	Horizontal displacement	Dist. in 1/8" increments
	Vrt	Vertical displacement	1 0 to 1/8 inch
Fe Element	Fe	Ferrous element	Not applicable
Joints Failed	MoCrk	Mortar Cracked	Area in sq. ft.
	MoF	Mortar Failed	Percentage
	MoMf	Mortar Missing	Length in ft., ft.
	ShF	Sealant Failed	Length in ft., ft.
Rot	Rot	Wood Rot	Not applicable
Prev. Repairs	D	Dutchman sound	Not applicable
	GP	Glaze Patch	Size of repair in square inches
	GPF	Glaze Patch Failed	Not applicable
	PF	Patch Failed	Not applicable
Soiled/Stained	P	Patch sound	Not applicable
	Bio	Biological growth	Area in sq. ft.
	Blk	Black Crusts	Area in sq. ft.
	Cem	Cementitious	Area in sq. ft.
	Lch	Leached Salts	Area in sq. ft.
	Pnt	Paint	Area in sq. ft.
Ret	Rust	Area in sq. ft.	

SURVEY CODES, CONTINUED			
Spalls	B	Bonded	Size of spall in square inches
	I	Incipient	Not applicable
	M	Missing	Not applicable
	MS	Missing + Steel	Not applicable
Surface Loss	Chp	Chipped	Depth of loss in 1/8" increments
	Glz	Glaze loss	Area in sq. ft.
Unsecured	Haz	Hazardous	Not applicable
	Hol	Hollow	Area in sq. ft.
	M	Missing	Area in sq. ft.

Annotations are comprised of text labels and graphical symbols. Four types of graphical symbols are used: --Target Symbols depict faults having discrete locations, such as spalls, individual failed fasteners, or punctures in sheet metal. --Box Symbols are rectangular symbols delineating conditions that span an area too large to be effectively represented with target symbols. --Polyline Symbols depict cracks and specific joint conditions.

Each text label includes a fault code describing the type of condition, and if applicable, a severity code and Picture Link.

This target symbol indicates a 20 square inch spall, which was removed during the survey and photographed.

This box symbol indicates an area of biological soiling, which was not photographed.

This polyline indicates a crack system following a joint path, 3/16 inch wide, which was photographed.

